

Item 553

Storm Water Pollution Prevention Plan (SW3P)

This item shall govern preparation, maintenance and implementation of the SW3P, and complying with Texas Commission on Environmental Quality (TCEQ) regulations; Texas Pollution Discharge Elimination System (TPDES) General Permit requirements (Permit No. TXR150000), and the City's Stormwater Compliance with Construction Activity Ordinance 94002 to include submittal and termination of permit notifications.

GENERAL NOTES:

The Contractor shall be the operator as defined by TPDES General Permit. The contractor shall comply with all TPDES General Permit requirements to include preparation, maintenance and implementation of the SW3P.

The Contractor shall submit all notifications and pay all associated fees required by the TPDES General Permit. The contractor shall provide the City Inspector copies of any submitted notifications and associated fee checks.

The Contractor's temporary control measures shall be installed and maintained throughout the construction contract and coordinated with proposed or existing permanent pollution control features to assure effective and continuous water pollution control throughout the construction and post construction period. The Contractor will maintain and inspect the temporary control measures in accordance with the TPDES General Permit requirements.

The control measures may include, but not limited to: sediment control fences, inlet protection, baled hay, rock filter dams, dikes, swales, construction exits, soil retention blanket, sediment traps and basins, or non-structural water pollution controls. The Contractor is responsible for any type of disastrous event resulting from negligence in providing the appropriate devices to prevent the contamination of storm water sewers and flooding on the roadway and private properties, in an event of a rainstorm.

CONSTRUCTION NOTES:

The Contractor shall provide control measures to prevent or minimize the impact to the existing municipal separate storm water system. This SW3P is to be adjusted and updated as the

project progresses to meet compliance with permit and ordinance.

POST CONSTRUCTION NOTES:

Contractor shall be responsible for the removal and appropriate disposal of any project control measures not incorporated as a permanent control when final stabilization has been obtained on the project.

MEASUREMENT:

This item will be measured by "Lump Sum" as indicated on plans.

PAYMENT:

This item shall be paid as "Lump Sum". This price shall be full compensation for furnishing all labor, materials, supplies, equipment and incidentals necessary to include payment of all permit fees. The "Lump Sum" price shall also be full compensation for removal and replacement and proper disposal of control measures not incorporated as permanent control measures. The lump sum will be pro-rated based on the number of calendar days in the project contract. Failure to complete the work within time allowed in the project contract due to approving designs, testing, material shortages, closed construction season, curing periods, and testing periods will not qualify for additional compensation.